



City of Vancouver *Zoning and Development By-law*

Community Services, 453 W. 12th Ave Vancouver, BC V5Y 1V4 ☎ 604.873.7344 fax 873.7060

planning@city.vancouver.bc.ca

CD-1 (170)

2675 Oak Street

By-law No. 5863


(Being a By-law to Amend By-law 3575, being the Zoning and Development By-law)

Effective January 8, 1985

(Amended up to and including By-law No. 8169, dated March 14, 2000)

- 1 *[Section 1 is not reprinted here. It contains a standard clause amending Schedule D (Zoning District Plan) to reflect this rezoning to CD-1.]*
- 2 The area shown included within the heavy black outline on Schedule “A” is rezoned to CD-1, and the only uses permitted within the said area, subject to such conditions as Council may by resolution prescribe, and the only uses for which development permits will be issued are:
- (a) General Office; [7002; 92 07 07]
 - (b) Accessory uses customarily ancillary to the above uses.
- 3 **Floor Space Ratio**
The floor space ratio shall not exceed 0.883, measured in accordance with the provisions of the C-2 District Schedule.
- 3.1 Where exterior walls greater than 152 mm in thickness have been recommended by a Building Envelope Professional as defined in the Building By-law, the area of the walls exceeding 152 mm, but to a maximum exclusion of 152 mm thickness, shall be excluded in the computation of floor space ratio, except that this section shall not apply to walls in existence prior to March 14, 2000. [8169; 00 03 14]
- 4 **Height**
The maximum building height, measured in accordance with the applicable provisions of the Zoning and Development By-law, shall be 14.630 m (48.00 ft.).
- 5 **Off-street Parking**
A minimum of 16 off-street parking spaces shall be provided. [7002; 92 07 07]
- 6 *[Section 6 is not reprinted here. It contains a standard clause including the Mayor and City Clerk’s signatures to pass the by-law and to certify the by-law number and date of enactment.]*

Note: *Information included in square brackets [] identifies the by-law numbers and dates for the amendments to By-law No. 5863 or provides an explanatory note.*



The property outlined in black (■) was rezoned:
 From **RM-3** to **CD-1** by By-law No. 5863

CD-1 (170) 2675 Oak St.	date prepared: Dec. 1992	
	sectional(s): N-13	
City of Vancouver Planning Department	scale: 1:2000	