



City of Vancouver *Zoning and Development By-law*

Community Services, 453 W. 12th Ave Vancouver, BC V5Y 1V4 ☎ 604.873.7344 fax 604.873.7060
planning@vancouver.ca

CD-1 (410)

7250 Oak Street

By-law No. 8457

(Being a By-law to Amend By-law 3575, being the Zoning and Development By-law)

Effective April 9, 2002

(Amended up to and including By-law No. 9674, dated June 24, 2008)

1 *[Section 1 is not reprinted here. It contains a standard clause amending Schedule D (Zoning District Plan) to reflect this rezoning to CD-1.]*

2 Uses

The area shown included within the heavy black outline on Schedule A shall be more particularly described as CD-1(410), and the only uses permitted within the outlined area, subject to such conditions as Council may by resolution prescribe, and the only uses for which development permits will be issued, are

- (a) Seniors Supportive or Assisted Housing;
- (b) Community Care Facility - Class B except that all persons in care in the facility must be 65 years or older, the facility must provide shared kitchens, dining and amenity areas, and staff may provide care, supervision, guidance or counseling related to physical disabilities and to mental disabilities arising from Alzheimer's Disease, senile dementia, or other forms of memory impairment, [9674; 08 06 24]
- (c) Parking Area on grade limited to space for parking no more than 18 motor vehicles ancillary to the principal use on that portion of PID: 025-372-351, Lot 1, Block 16A, District Lot 526, Plan LMP53218 not included within the heavy black outline on Schedule "A" so long as permitted by development permits limited to periods not exceeding five years, and [8522; 02 07 25]
- (d) Accessory Uses customarily ancillary to the above uses.
[8824; 04 04 06]

3 Floor Space Ratio

3.1 The floor space ratio must not exceed 1.10.

3.2 The following will be included in the computation of floor space ratio:

- (a) all floors having a minimum ceiling height of 1.2 m, including earthen floor, both above and below ground level, to be measured to the extreme outer limits of the building, and
- (b) stairways, fire escapes, elevator shafts and other features which the Director of Planning considers similar, to be measured by their gross cross-sectional areas and included in the measurements for each floor at which they are located.

3.3 The following must be excluded from the computation of floor space ratio:

- (a) open residential balconies or sun decks, open porte cochere to a maximum exclusion of 75.62m², and any other appurtenances which, in the opinion of the Director of Planning, are similar to the foregoing, [8522; 02 07 25]
- (b) patios and roof gardens, provided that the Director of Planning first approves the design of sunroofs and walls,
- (c) where floors are used for off-street parking and loading, the taking on or discharging of passengers, bicycle storage, heating and mechanical equipment, or uses which, in the opinion of the Director of Planning, are similar to the foregoing, those floors or portions thereof so used, which
 - (i) are at or below the base surface, provided that the maximum exclusion for a parking space shall not exceed 7.3 m in length, or

Note: *Information included in square brackets [] identifies the by-law numbers and dates for the amendments to By-law No. 8457 or provides an explanatory note.*

- (ii) are above the base surface and where developed as off-street parking are located in an accessory building situated in the rear yard, provided that the maximum exclusion for a parking space shall not exceed 7.3 m in length,
- (d) amenity areas, including day care facilities, recreation facilities, library, lounges, activity and meeting rooms, to a maximum total of 10 percent of the total building floor area,
- (e) areas of undeveloped floors which are located:
 - (i) above the highest storey or half-storey and to which there is no permanent means of access other than a hatch, or
 - (ii) adjacent to a storey or half-storey with a ceiling height of less than 1.2 m,
- (f) all residential storage space above or below base surface, except that if the residential storage space above base surface exceeds 3.7 m² per dwelling unit, there will be no exclusion for any of the residential storage space above base surface for that unit; [8760; 03 12 09] and
- (g) where exterior walls greater than 152 mm in thickness have been recommended by a Building Envelope Professional as defined in the Building By-law, the area of the walls exceeding 152 mm, but to a maximum exclusion of 152 mm thickness, except that this clause shall not apply to walls in existence prior to March 14, 2000.

4 Height

The Director of Planning may permit a maximum building height measured above the base surface of 14.63 m or four storeys, provided the following are taken into consideration:

- (a) the relationship of the development with nearby residential buildings and sites,
- (b) the height, bulk, location and overall design of the building and its effect on the site, surrounding buildings, streets and existing views, and
- (c) the submission of any advisory group, property owner or tenant.

5 Setbacks

5.1 The minimum setback of a building is 12.2 m from the west property boundary.

5.2 The minimum setback of a building is 6.55 m from the south property boundary. [8461; 02 04 23]

5.3 The minimum setback of a building is 6.1 m from the north property boundary of the area shown within the heavy black outline on Schedule "A".

6 Off-street Parking and Loading

Parking, loading and bicycle spaces must be provided, developed and maintained in accordance with the applicable provisions of the Parking By-law, except that a minimum of one off-street parking space for every four beds must be provided, and a minimum of one disability space for every 15 parking spaces must be provided, with a minimum provision of two disability spaces.

7 Acoustics


All development permit applications require evidence in the form of a report and recommendations prepared by a person trained in acoustics and current techniques of noise measurement, demonstrating that the noise levels in those portions of the dwelling units listed below do not exceed the noise level set opposite such portions. For the purposes of this section, the noise level is the A-weighted 24-hour equivalent (Leq) sound level and is defined simply as noise level in decibels.

Portions of dwelling units	Noise levels (Decibels)
bedrooms	35
living, dining, recreation rooms	40
kitchen, bathrooms, hallways	45

8 *[Section 8 is not reprinted here. It contains a standard clause including the Mayor and City Clerk's signature to pass the by-law and certify the by-law number and date of enactment.]*

By-law No. 8457 being a By-law to amend By-law No. 3575

being the Zoning & Development By-law



The property outlined in black () is rezoned:

From **RS-1** to **CD-1**

Z-519

RZ - 7250 Oak Street

map: 1 of 1

scale: 1:2000



City of Vancouver